GENERAL NOTES:

I. CONTRACTOR IS REQUIRED TO VISIT SITE AND FAMILIARIZE HIM/HERSELF WITH THE PROJECT PRIOR TO BIDDING.

2. THE CONTRACTOR SHALL COMPLY WITH ALL FEDERAL AND STATE REGULATIONS CONCERNING NOTIFICATION TO THE REGULATORY AUTHORITIES OF ANY AND ALL BUILDING RENOVATIONS AND/OR

3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONSTRUCTION MONITORING AND NOTIFYING THE ENGINEER OF RECORD AT LEAST 72 HOURS PRIOR TO COMMENCEMENT OF CONSTRUCTION AND CONCLUSION OF CONSTRUCTION, AS WELL AS SUPPLYING CLEAR AND LEGIBLE REVISIONS TO THE CONSTRUCTION PLANS FOR USE DURING AS-BUILT CERTIFICATION. 4. ALL DISTURBED AREAS WHICH ARE NOT PAVED ARE TO BE STABILIZED WITH SEEDING, FERTILIZER & MULCH, HYDROSFED AND/OR SOD (RECOMMEND CENTIPEDE, PENSACOLA BAHLA OR BERMUDA SOD), POND AND SWALE TOPS AND SIDES SHALL BE SODDED AND PINNED. ALL SOD PLACED ON SIDE SLOPES 4 TO 1 OR GREATER SHALL BE PINNED.

6. AFTER THE SITE HAS BEEN BROUGHT TO PROPER GRADE FOR PLACEMENT OF TOPSOIL AND IMMEDIATELY PRIOR TO DUMPING AND SPREADING THE TOPSOIL, THE SUBGRADE SHALL BE LOOSENED BY DISKING OR SCARIFYING TO A DEPTH OF 2" TO INSURE BONDING OF THE TOPSOIL AND SODDING.

7. TOPSOIL SHALL NOT BE PLACED IN A MUDDY CONDITION, WHEN THE SUBGRADE IS EXCESSIVELY WET, OR IN A CONDITION THAT MAY OTHERWISE BE DETRIMENTAL TO PROPER GRADING AND

8. THE TOPSOIL SHALL BE UNIFORMLY DISTRIBUTED TO A MINIMUM COMPACTED DEPTH OF 3".

5. WHERE SOD IS BEING INSTALLED. TOPSOIL SHALL BE USED AS A BASE AT LEAST 3" DEEP

9. ANY IRREGULARITIES IN THE SURFACE RESULTING FROM TOPSOILING OR OTHER OPERATIONS SHALL BE CORRECTED IN ORDER TO PREVENT THE FORMATION OF DEPRESSIONS OR WATER POCKETS. 10. COMPACT THE TOPSOIL ENOUGH TO ENSURE GOOD CONTACT WITH THE UNDERLYING SOIL AND TO OBTAIN A LEVEL SEED BED FOR THE ESTABLISHMENT OF HIGH MAINTENANCE TURF. AVOID

11. CONTRACTOR IS TO MAINTAIN SODDING AND GRASSING BY WATERING, FERTILIZING, WEEDING, MOWING, TRIMMING AND OTHER OPERATIONS SUCH AS ROLLING, RE-GRADING AND REPLANTING AS REQUIRED TO ESTABLISH GRASSED/SODDED AREAS FREE OF ERODED OR BARE AREAS AND REPLACE ANY REJECTED MATERIALS PROMPTLY FROM THE SITE, CONTRACTOR IS TO INCLUDE COST OF

12. CONTRACTOR SHALL INSTALL PRIOR TO THE START OF CONSTRUCTION AND MAINTAIN DURING CONSTRUCTION ALL SEDIMENT CONTROL MEASURES AS REQUIRED TO RETAIN ALL SEDIMENTS ON THE SITE. IMPROPER SEDIMENT CONTROL MEASURES MAY RESULT IN A CODE ENFORCEMENT VIOLATION. 13. DEVELOPER/CONTRACTOR SHALL RESHAPE PER PLAN SPECIFICATIONS, CLEAN OUT ACCUMULATED SILT, AND STABILIZE ANY DISTURBED AREAS FOUND IN RETENTION POND AT END OF CONSTRUCTION WHEN ALL DISTURBED AREAS HAVE BEEN STABILIZED AND PRIOR TO REQUEST FOR INSPECTION

14. CONTRACTOR SHALL MAINTAIN RECORD DRAWINGS DURING CONSTRUCTION AND PROVIDE A TOPOGRAPHICAL SURVEY (CERTIFIED BY A STATE OF FLORIDA LICENSED SURVEYOR) OF THE PROJECT AREA WHICH ILLUSTRATES AS—BUILT CONDITIONS OF ALL WORK AND SITE IMPROVEMENTS, INCLUSIVE OF PIPING, DRAINAGE STRUCTURES, STORMWATER POND TOPOGRAPHY, SITE ELEVATIONS AND GRADING, OUTLET STRUCTURES, DIMENSIONS, ETC. THESE RECORD DRAWINGS ARE TO BE PROVIDED TO THE PROJECT ENGINEER PRIOR TO REQUESTING FINAL INSPECTION.

15. THE OWNER OR HIS AGENT SHALL ARRANGE/SCHEDULE WITH THE COUNTY INSPECTIONS OFFICE (850-595-3569) AN INSPECTION OF THE EROSION AND SEDIMENT CONTROL DEVICES PRIOR TO CONSTRUCTION, UNDERGROUND DRAINAGE STRUCTURES PRIOR TO BURIAL, ALL INTERMEDIATE INSPECTIONS AND THE FINAL INSPECTION OF THE DEVELOPMENT UPON COMPLETION. AS-BUILT CERTIFICATION IS REQUIRED PRIOR TO REQUEST FOR FINAL INSPECTION/APPROVAL.

16. EROSION SHALL BE CONTROLLED BY THE USE OF A HAY BALE BARRIER/SILT FENCE AS SHOWN ON PLANS AND SHALL BE SETUP PRIOR TO COMMENCING CONSTRUCTION. THE EROSION CONTROL BARRIER SHALL BE MAINTAINED THROUGHOUT CONSTRUCTION BY THE CONTRACTOR. UPON COMPLETION OF THE PROJECT, THE DETENTION AREA SHALL BE CLEANED OF SILT & STABILIZATION OF ALL DISTURBED AREAS SHALL BE ACCOMPLISHED.

17. CONTRACTOR SHALL NOTIFY SUNSHINE ONE UTILITIES (1-800-432-4770) TWO FULL BUSINESS DAYS IN ADVANCE PRIOR TO DIGGING WITHIN R/W.

18. ALL ASPECTS OF THE STORMWATER/DRAINAGE COMPONENTS AND/OR TRANSPORTATION COMPONENTS SHALL BE COMPLETED PRIOR TO REQUESTING A FINAL INSPECTION AND ISSUANCE OF A

19. NO DEVIATIONS OR REVISIONS FROM THESE PLANS BY THE CONTRACTOR SHALL BE ALLOWED WITHOUT PRIOR APPROVAL FROM BOTH THE DESIGN ENGINEER AND THE ESCAMBIA COUNTY. ANY DEVIATIONS MAY RESULT IN DELAYS IN OBTAINING A CERTIFICATE OF OCCUPANCY.

20. RIGHT-OF-WAY SHOULDER STABILIZATION SHALL BE IN ACCORDANCE WITH F.D.O.T. STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION (LATEST EDITION). 21. ALL EXCESS MATERIAL SHALL BE REMOVED FROM THE SITE AND DISPOSED OF IN A LEGAL MANNER BY THE CONTRACTOR. IF THERE WILL BE TEMPORARY STOCKPILING OF MATERIALS ON THE SITE, THESE AREAS SHOULD CONTAIN EROSION CONTROL BMP'S (e.g. SILT FENCE, HAY BALES, ETC) AS NECESSARY.

22. ANY DAMAGE TO EXISTING ROADS DURING CONSTRUCTION WILL BE REPAIRED BY THE DEVELOPER PRIOR TO FINAL "AS-BUILT" SIGN OFF FROM THE COUNTY.

23. ALL BUILDING ROOF DRAINS, DOWN SPOUTS OR GUTTERS SHALL BE ROUTED TO CARRY ALL STORMWATER RUNOFF TO ON-SITE RETENTION BASIN.

24. CONTRACTOR TO COORDINATE WITH LOCAL UTILITY COMPANIES FOR REMOVAL AND RELOCATION OF EXISTING UTILITY POLES, AERIAL LINES, WATER LINES, GAS LINES AND OTHER UTILITIES AS

25. CONTRACTOR IS RESPONSIBLE FOR LOCATING AND VERIFYING ALL EXISTING UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION AND IS RESPONSIBLE FOR ANY DAMAGE TO THEM DURING

26. UTILITY LOCATIONS ARE APPROXIMATE BASED ON LOCATION OF ABOVE GROUND APPURTENANCES, AND AS TAKEN FROM THE SURVEY. UNDERGROUND UTILITIES NOT SHOWN HEREIN MAY EXIST. 27. CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR AND TAKE ALL PRECAUTIONS NECESSARY TO AVOID DAMAGE TO ADJACENT PROPERTIES DURING THE CONSTRUCTION PHASES OF THIS

28. CONTRACTOR SHALL COMPLY WITH ANY TESTING REQUIRED BY STATE AND LOCAL GOVERNING AGENCIES SUCH AS ASPHALT CORES AND SUB-BASE/BASE COMPACTION TESTING

29. THE CONTRACTOR SHALL NOTIFY THE OWNER OF ANY CONFLICTS BETWEEN VENDOR DRAWINGS, EXISTING CONDITIONS AND THE CONSTRUCTION DOCUMENTS.

30. CONTRACTOR TO PROVIDE PROTECTION TO TREES THAT ARE TO REMAIN VIA TREE PROTECTION BARRIERS. REFER TO EROSION CONTROL PLAN FOR MORE INFORMATION. 31. TRENCHING OR GRADING AROUND TREES TO REMAIN SHALL BE AWAY FROM THE TREE IN A MANNER TO CAUSE NO DAMAGE TO THE TREE'S CRITICAL ROOT ZONE. THE CRITICAL ROOT ZONE IS REPRESENTED BY A CIRCLE, CENTERED ON THE TREE TRUNK AND HAVING A RADIUS OF ONE FOOT FOR EACH ONE INCH OF TRUNK DIAMETER (DBH). REFER TO LANDSCAPING PLAN FOR

SIGNAGE:

NO NEW PROPOSED SIGNAGE WILL BE PART OF THIS DEVELOPMENT

JURISDICTIONAL CONTACTS:

ESCAMBIA COUNTY DEVELOPMENT SERVICES 3363 WEST PARK PLACE

PENSACOLA, FL 32505 PHONE NO.: (850)-595-3475 FAX NO.: (850)-595-3481

EMERALD COAST UTILITIES AUTHORITY

9255 STURDEVANT STREET PENSACOLA. FL 32514 PHONE NO.: (850)-476-5110 FAX NO.: 850-494-7346

NORTHWEST FLORIDA WATER MANAGEMENT DISTRICT 700 US HIGHWAY 331 SOUTH

DEFUNIAK SPRINGS, FL 32435 PHONE NO.: (850)-951-4660 FAX NO.: (850)-892-8007

FLORIDA DEPARTMENT OF ENVIRONMENTAL PROTECTION 2600 BLAIR STONE ROAD

TALLAHASSEE, FL 32399 PHONE NO.: (866)-336-6312 FAX NO.: (850)-297-1211

PROJECT DIRECTORY:

CIVIL ENGINEER HAMMOND ENGINEERING, INC. 3802 NORTH 'S' ST. PENSACOLA, FL 32505 PHONE NO.: (850)-434-2603

FAX NO.: (850)-434-2650

SURVEYOR

360 SURVEYING SERVICES, INC. 213 A SOUTH BAYLEN STREET PENSACOLA, FL 32502 PHONE NO.: (850)-857-4400 FAX NO.: (850)-478-4924

DATE REVISIONS NO. REVISED PLANS AS PER ESCAMBIA COUNTY DRC REVIEW COMMENTS 01/18/2021

SITE DEVELOPMENT PLANS FOR

WOODY CUSHING ROOFING ACCESSORY BUILDING

SECTION 46, TOWNSHIP 1 SOUTH, RANGE 30 WEST ESCAMBIA COUNTY, FLORIDA

> 525 MICHIGAN AVENUE PENSACOLA. FL 32505

OWNER/DEVELOPER: WOODY CUSHING ROOFING, INC. C/O WOODROW CUSHING 525 W. MICHIGAN AVE. PENSACOLA, FL 32505 (850)-478-8534

PROPERTY I.D NO.: 46-1S-30-2001-021-052 ZONING DESIGNATION: HC/LI ADJACENT ZONING: HC/LI FLU DESIGNATION: COM ADJACENT FLU: COM

INDEX_OF_DRAWINGS: $C1 \sim COVER$ C2 ~ EXISTING CONDITIONS ~ DEMOLITION & EROSION CONTROL PLAN ~ SITE & GRADING PLAN \sim UTILITY PLAN C6 ~ LANDSCAPING PLAN ~ CONSTRUCTION DETAILS ~ CONSTRUCTION DETAILS

HAMMOND ENGINEERING, INC. FLORIDA AUTHORIZATION NO. 9130 ALABAMA AUTHORIZATION NO. 3277 3802 NORTH "S" STREET PENSACOLA, FLORIDA 32505 850-434-2603

> FAX 850-434-2650 TOM@SELANDDESIGN.COM

REVISED JANUARY 18, 2021 HEI PROJECT #: 20-039

- 32. CONTRACTOR SHALL CONSTRUCT TEMPORARY MEASURES AND SUPPORT TO ACCESS THE SITE AND SHALL INCLUDE THE COST FOR SAME IN THE BID. CONTRACTOR SHALL REPAIR ANY DAMAGE TO THE SATISFACTION OF THE OWNER AND/OR GOVERNING AGENCY.
- 33. CONTRACTOR SHALL COORDINATE HIS WORK AND COOPERATE WITH OTHER CONTRACTORS WORKING AROUND THE PROJECT AREA.
- 34. THE CONTRACTOR SHALL BE RESPONSIBLE FOR REPORTING SPILLS OF POTENTIALLY HAZARDOUS SUBSTANCES (I.e. GASOLINE, DIESEL FUEL, HYDRAULIC FLUID, ETC.) TO THE APPROPRIATE STATE (FDEP STATE WARNING POINT 1-800-320-0519) AND LOCAL (ESCAMBIA COUNTY HEALTH DEPT. 850-595-6700) AGENCIES.
- 35. SOLID WASTE SHALL BE KEPT IN AN APPROVED DUMPSTER THROUGHOUT CONSTRUCTION ACTIVITIES
- 36. ALL VALVE BOXES SHALL BE SET FLUSH WITH GRADE(IF APPLICABLE).
- 37. ADEQUATE PROVISIONS SHALL BE MADE FOR FLOW OF SEWERS, DRAINS, AND WATER COURSES ENCOUNTERED DURING CONSTRUCTION.
- 38. THE CONTRACTOR SHALL FLUSH AND CLEAN ALL STORMWATER PIPES AND STRUCTURES AT END OF CONSTRUCTION AFTER ALL DISTURBED AREAS HAVE BEEN STABILIZED.
- 39. PLACEMENT OF UNDERGROUND SYSTEMS, IRRIGATION, SEWER, WATER, DRAINAGE, ELECTRICAL, GAS, ETC. SHALL BE COMPLETED PRIOR TO LANDSCAPE INSTALLATION. 40. PROPERTY OBSTRUCTIONS WHICH ARE TO REMAIN IN PLACE SUCH AS BUILDINGS, SEWERS, DRAINS, WATER OR GAS PIPES, ELECTRICAL, CONDUITS, POLES, WALLS, POSTS, ETC. ARE TO BE CAREFULLY PROTECTED AND ARE NOT TO BE DISPLACED UNLESS NOTED.
- 41. THE CONTRACTOR SHALL ADHERE TO ALL LOCAL, STATE AND FEDERAL AGENCIES RULES CONCERNING SAFETY.
- 42. CONTRACTOR SHALL PLACE AND MAINTAIN ADEQUATE BARRICADES, CONSTRUCTION SIGNS, FLASHING LIGHTS, TORCHES, RED LANTERNS, AND GUARDS DURING PROGRESS OF CONSTRUCTION WORK AND UNTIL IT IS SAFE FOR BOTH PEDESTRIAN AND VEHICULAR TRAFFIC
- 43. CONTRACTOR SHALL INCLUDE IN HIS BID ANY COST ASSOCIATED WITH DE-WATERING AND DE-MUCKING FOR INSTALLATION OF REQUIRED INFRASTRUCTURE (IF APPLICABLE).
- 44. THE CONTRACTORS MEANS AND METHODS OF GROUNDWATER DE-WATERING SHALL COMPLY WITH ALL REGULATORY REQUIREMENTS FOR THE TEMPORARY DIVERSION OF GROUNDWATER AND ITS DISCHARGE, INCLUDING FAC CHAPTER 62-621.300(2) "GENERIC PERMIT FOR THE DISCHARGE OF PRODUCED GROUNDWATER FROM ANY NON-CONTAMINATED SITE ACTIVITY" (IF
- 45. CONTRACTOR SHALL INCLUDE IN HIS BID ANY COST ASSOCIATED WITH SELECT BACKFILL FOR INSTALLATION OF ANY INFRASTRUCTURE.

46. CONTRACTOR SHALL CLEAN UP ENTIRE SITE INCLUDING STAGING AREAS AT LEAST TWO TIMES PER WEEK. THIS SHALL INCLUDE LOCATING TRASH/SCRAP RECEPTACLES AT APPROPRIATE LOCATIONS AROUND THE SITE. CONTRACTOR SHALL PICK UP ALL ROCKS, METAL, PIPE, NAILS, NUTS, BOLTS, BOARDS, PAPER, TRASH, ETC. AT LEAST TWICE A WEEK.

47. CONTRACTOR SHALL RESTORE ALL STAGING AREAS TO AS GOOD AS OR BETTER CONDITION THAN EXISTED PRIOR TO CONSTRUCTION. THIS INCLUDES IRRIGATION AND SOD REPLACEMENT OF NECESSARY. ANY DISTURBED AREAS THAT WILL BE LEFT EXPOSED MORE THAN 20 DAYS AND NOT SUBJECT TO CONSTRUCTION TRAFFIC WILL IMMEDIATELY RECEIVE A TEMPORARY SEEDING. IF THE SEASON PREVENTS THE ESTABLISHMENT OF A TEMPORARY COVER, THE DISTURBED AREAS WILL BE MULCHED WITH STRAW, OR EQUIVALENT MATERIAL, AT A

48. IMMEDIATELY FOLLOWING INITIAL DISTURBANCE OR ROUGH GRADING, ALL CRITICAL AREAS SUBJECT TO EROSION (i.e. STEEP SLOPES AND ROADWAY EMBANKMENTS) WILL RECEIVE A TEMPORARY SEEDING IN COMBINATION WITH STRAW MULCH OR A SUITABLE EQUIVALENT, AT A THICKNESS OF TWO (2) TO FOUR (4) INCHES MIXED WITH THE TOP TWO (2) INCHES OF

49. ANY SLOPES RECEIVING INFRASTRUCTURE INSTALLATION WILL BE BACKFILLED AND STABILIZED DAILY, AS THE INSTALLATION PROCEEDS (i.e. SLOPES GREATER THAN 3:1) 50. SHOULD THE CONTROL OF DUST AT THE SITE BE NECESSARY, THE SITE WILL BE SPRINKLED UNTIL THE SURFACE IS WET, TEMPORARY VEGETATION COVER SHALL BE ESTABLISHED OR MULCH SHALL BE APPLIED IN ACCORDANCE WITH STANDARDS FOR EROSION CONTROL

51. ALL SOIL WASHED, DROPPED, SPILLED OR TRACKED OUTSIDE THE LIMITS OF DISTURBANCE OR ONTO PUBLIC RIGHT OF WAY WILL BE REMOVED IMMEDIATELY.

52. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY EROSION OR SEDIMENTATION THAT MAY OCCUR BELOW STORMWATER OUTFALLS OR OFFSITE AS A RESULT OF CONSTRUCTION OF

53. ALL SOIL STOCKPILES ARE TO BE TEMPORARILY STABILIZED IN ACCORDANCE WITH SOIL EROSION AND SEDIMENT CONTROL NOTE #48 ABOVE.

54. THE SITE SHALL AT ALL TIMES BE GRADED AND MAINTAINED SUCH THAT ALL STORMWATER RUNOFF IS DIVERTED TO SOIL EROSION AND SEDIMENT CONTROL FACILITIES.

55. ALL SEDIMENTATION STRUCTURES SHALL BE INSPECTED AND MAINTAINED REGULARLY

56. ANY DIRT THAT RUNS OFF OF THE PROJECT SITE ONTO PUBLIC STREETS SHALL BE REMOVED AND CLEANED IMMEDIATELY. FAILURE TO COMPLY CAN RESULT IN CODE ENFORCEMENT

57. ANY AREAS USED FOR THE CONTRACTORS STAGING, INCLUDED BUT NOT LIMITED TO, TEMPORARY STORAGE OF STOCKPILED MATERIALS (I.e. CRUSHED STONE, QUARRY PROCESS STONE, SELECT FILL, EXCAVATED MATERIALS, ETC.) SHALL BE ENTIRELY PROTECTED BY A SILT FENCE ALONG THE LOW ELEVATION SIDE TO CONTROL SEDIMENT RUNOFF.

58. ALL CONSTRUCTION METHODS AND MATERIALS MUST CONFORM TO CURRENT ESCAMBIA COUNTY, FDEP, AND ECUA STANDARDS AND REQUIREMENTS

59. FOR SITES WITH DISTURBANCE EXCEEDING 1 ACRE... TO COMPLY WITH NPDES REQUIREMENTS, THE CONTRACTOR SHALL SUBMIT AN NPDES NOTICE OF INTENT TO FDEP A MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION. ADDITIONALLY, ALL EROSION CONTROL MEASURES SHALL BE INSPECTED AFTER EACH 1/2" RAINFALL EVENT OR AT LEAST WEEKLY. A CERTIFIED STORMWATER MANAGEMENT INSPECTOR SHALL DOCUMENT SUCH INSPECTIONS AND EROSION CONTROL EFFORTS. INSPECTION RECORDS SHOULD BE ON HAND AT ALL TIMES AND PROVIDED TO ANY FDEP REPRESENTATIVE THAT MAY VISIT THE SITE DURING CONSTRUCTION.


60. THE PROJECT ENGINEER (ENGINEER OF RECORD) SHALL PROVIDE TO ESCAMBIA COUNTY "AS-BUILT" RECORD DRAWINGS FOR VERIFICATION AND APPROVAL ONE WEEK PRIOR TO REQUESTING A FINAL INSPECTION AND CERTIFICATE OF OCCUPANCY, OR PROVIDE "AS-BUILT" CERTIFICATION THAT THE PROJECT CONSTRUCTION ADHERES TO THE PERMITTED PLANS AND SPECIFICATIONS. THE "AS-BUILT" CERTIFICATION OR "AS-BUILT" RECORD DRAWINGS MUST BE SIGNED, SEALED AND DATED BY A REGISTERED FLORIDA PROFESSIONAL ENGINEER. 61. RETENTION/DETENTION AREAS SHALL BE SUBSTANTIALLY COMPLETE PRIOR TO ANY CONSTRUCTION ACTIVITIES THAT MAY INCREASE STORMWATER RUNOFF RATES. THE CONTRACTOR SHALL CONTROL STORMWATER DURING ALL PHASES OF CONSTRUCTION AND TAKE ADEQUATE MEASURES TO PREVENT THE EXCAVATED POND FROM BLINDING DUE TO SEDIMENTS.

FLOOD ZONE DATA

62. REFER TO BUILDING PLANS FOR ADDITIONAL INFORMATION.

THE SUBJECT PROPERTY SHOWN HEREON IS LOCATED IN FLOOD ZONE X, (MINIMAL RISK AREAS OUTSIDE THE 1-PERCENT AND .2-PERCENT-ANNUAL-CHANCE FLOODPLAINS. NO BFE'S OR BASE FLOOD DEPTHS ARE SHOWN WITHIN THESE ZONES), AS DETERMINED FROM THE FEDERAL EMERGENCY MANAGEMENT AGENCY FLOOD INSURANCE RATE MAP OF ESCAMBIA COUNTY, FLORIDA, COMMUNITY 120080, FIRM MAP PANEL NUMBERS 12033C0360G, MAP REVISIONS DATED SEPTEMBER 29, 2006. MAP REVISION DAT

COMMUNITY ZONE(S) | COMMON NUMBER NUMBER(S) X 120080 12033C SEPTEMBER 29, 2006





LOCATION


PROJECT


GRAPHIC SCALE 22" \times 34": 1 inch = 1500 ft.


11" x 17": 1 inch = 3000 ft.




























TREE PROTECTION BARRICADES SHOULD BE PLACED AT THE PERIMETER OF EACH PROTECTED TREE'S CRITICAL ROOT ZONE. THE CRITICAL ROOT ZONE (CRZ) IS REPRESENTED BY A CIRCLE, CENTERED ON THE TREE TRUNK AND HAVING A RADIUS OF ONE FOOT FOR EACH ONE INCH OF TRUNK DIAMETER (DBH)

NO UN-PERMITTED GRADING OR CLEARING BY HEAVY EQUIPMENT SHOULD HAPPEN UNDER THE CRITICAL ROOT ZONE OF PROTECTED TREES TO REMAIN ON THE SITE. STORAGE OF HEAVY EQUIPMENT SHALL NOT OCCUR UNDER THE CRITICAL ROOT ZONE OF PROTECTED TREES ON SITE.



PROPERLY CONSTRUCTED BARRICADE PROTECTS
THE TOTAL AREA WITHIN THE CRITICAL ROOT ZONE. CRITICAL ROOT ZONE OF A TREE IS REPRESENTED BY A CIRCLE, CENTERED ON THE TRE TRUNK AND HAVING A RADIUS OF ONE FOOT FOR EACH ONE INCH OF TRUNK DIAMETER (DBH

TREE PROTECTION BARRIER



SENSITIVE AREA/TREE PROTECTION BARRIER


1. ALL SENSITIVE AREAS SHALL BE PROTECTED INCLUDING DEEP EXCAVATIONS AND AS INDICATED ON PLANS. ALL TREES IN THE CONSTRUCTION AREA NOT SPECIFICALLY DESIGNATED FOR REMOVAL SHALL BE PRESERVED AND

PROTECTED WITH HIGH VISIBILITY FENCE AS PER PLAN. 3. TREE PROTECTION BARRIER SHOULD BE PLACED, AND MAINTAINED IN GOOD WORKING ORDER, AROUND THE PERIMETER OF EACH PROTECTED TREE'S CRITICAL ROOT ZONE (CRZ) OF ALL PROTECTED TREES MARKED FOR PRESERVATION PRIOR TO ANY LAND DISTURBANCE CONSISTENT WITH THE DEVELOPMENT PERMIT. SAFETY FENCE SHOULD BE FASTENED SECURELY TO THE T-POSTS

5. THE FENCING MUST REMAIN IN PLACE DURING ALL PHASES OF CONSTRUCTION; ANY CHANGE OF THE PROTECTIVE FENCING MUST BE APPROVED.

NO UN-PERMITTED GRADING OR CLEARING BY HEAVY EQUIPMENT SHOULD OCCUR UNDER THE CRITICAL ROOT ZONE OF PROTECTED TREES TO REMAIN ON THE SITE. STORAGE OF HEAVY EQUIPMENT SHALL NOT OCCUR UNDER THE CRITICAL ROOT ZONE OF PROTECTED TREES ON SITE.

7. ALL DAMAGED ROOTS ARE TO BE EXPOSED TO SOUND TISSUE AND SEVERED CLEANLY (NOT TORN). ROOTS SHALL BE PRUNED CLEANLY TO A DEPTH OF 18 INCHES BELOW THE EXISTING GRADE OR TO THE DEPTH OF DISTURBANCE IF LESS THAN 18 INCHES FROM EXISTING GRADE.




. TYPE III SILT FENCE TO BE USED AT MOST LOCATIONS. WHERE USED IN DITCHES, THE SPACING FOR TYPE III SILT FENCE SHALL BE IN ACCORDANCE WITH CHART 1 (FOUND BELOW)

2. TYPE IV SILT FENCE TO BE USED WHERE LARGE SEDIMENT LOADS ARE ANTICIPATED. SUGGESTED USE IS WHERE FILL SLOPE IS 1:2 OF STEEPER AND LENGTH OF SLOPE EXCEEDS 25'. AVOID USE WHERE THE DETAINED WATER MAY BACK INTO TRAVEL LANES OR ADJACENT PROPERTY.

3. DO NOT CONSTRUCT SILT FENCES ACROSS PERMANENT FLOWING WATER COURSES. SILT FENCES ARE TO BE USED AT UPLAND LOCATIONS AND TURBIDITY BARRIERS USED AT PERMENENT BODIES OF WATER.

4. WHERE USED AS SLOPE PROTECTION, SILT FENCE IS TO BE CONSTRUCTED ON 0% LONGITUDINAL GRADE TO AVOID CHANNELIZING RUNOFF ALONG THE LENGTH OF THE FENCE.

JOINING TWO SILT FENCES




TYPE III SILT FENCE


M


= 0 m


ILDINI DETAII


PROJECT NO: 20-039 SHEET: C7













TYPICAL LATERAL SEWER SERVICE


IOTES:


1. MAINTAIN 18" MINIMUM COVER OR USE 6 L.F. CONCRETE ENCASEMENT 2. ALL LATERALS TO BE 4" OF PVC 3034 DR SEWER PIPE UNLESS FLOW DICTATES A LARGER DIAMETER.

3. A CLEAN OUT SHALL BE PROVIDED WITHIN 5 FT OF BUILDING WHERE THE SEWER LATERAL EXITS










NOTE: ALL UTILITY DETAILS ILLUSTRATED PERTAIN TO ONSITE WORK ONLY. ALL UTILITY WORK WITHIN THE PUBLIC R/W SHALL BE PERFORMED IN ACCORDANCE WITH THE CURRENT EDITION OF THE ECUA ENGINEERING MANUAL. CONTRACTOR TO REFERENCE ECUA ENGINEERING MANUAL FOR CONSTRUCTION DETAILS AND PROCEDURES.



SIDEWALK DETAILS

**FIBER REINFORCED CONCRETE CAN BE USED IN LIEU OF WWF IF DESIRED

DESIGNED BY: RLS

CHECKED BY: TGH

DATE: 01/07/21

SCALE: AS SHOWN

NOT RELEASED FOR

CONSTRUCTION

BY: DATE:

DRAWN BY: CJG

SITE DEVELOPMENT

PLANS FOR

ROOFING

ROOFING

CONSTRUCTION

CONSTRUCTION

BY: DATE:

SHEET: C8

_ v w

 $\Sigma \subseteq \emptyset$

7

ENGINEE HORIZATII HORIZATII IRTH "S" (A, FLORII) 434-26(50-434-2